

1 070295

FEB 10 1987

15-083-20535-0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-20,535 *Docket # D-19, 112*
N/2 SE SW, SEC. 19, T 22 S, R 23 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Co., Inc.
Name & Address 1260 KSB Building
Wichita, KS 67801

990 feet from S section line
3300 feet from E section line

Lease Name Hays "A" Well # 2
County Hodgeman 155.03

Well Total Depth 4770 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 10 Month: 2 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 1670' Perfs at 1135-95', 1245-85'

1st plug pump 2 sx hulls and 100 sx cement,

2nd plug pump 200 sx cement down backside.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:30 p.m. Day: 10 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 120 sx cement.

8 5/8" annulus started to circulate shortly after start of pumping. Closed annulus
and pumped cement until cement started spraying from braden head.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-18-87

DIV. NO. 16143

FEB 17 1987
Signed Dan Jordan
CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)