

1030179

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,085-0000

SE SE _____, SEC. 30, T 22 S, R 17 ~~W~~

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8594

Lease Name Welsh Well # 1-30

Operator: T.D.R. Exploration Company

County Pawnee

Name & Address 3816 North Meridian

Well Total Depth 4460 ^{144.95} feet

Suite 113

Conductor Pipe: Size _____ feet

Oklahoma City, OK 73112

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 16 Month: May Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4395' CIBP at 3928-34 CIBP at 4238-42 Perfs 3832-42

1st plug sand back to 3780 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement

Plugging Proposal Received by Steve Belmont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45 am Day: 16 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4395' CIBT at 3928-34 CIBP at 4238-42 Perfs 3832-42

1st plug sanded back to 3780' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 700# and shut in pressure 300#

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

MAY 18 1984

(if additional description is necessary, use BACK of this CONSERVATION DIVISION
Wichita, Kansas
(did not) observe this plugging.

Signed Steve Belmont
(TECHNICIAN)

INVOICED

DATE 5-21-84

INV. NO. 1581

5-16