

11-22-87

To: 1 120053
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,270 - 0000

NW NW SE, SEC. 12, T 22 S, R 19 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Meckfessel Well # 1

Operator: Falcon Exploration Inc.

County Pawnee 149.60

Name & Address 125 North Market, Suite 1531

Well Total Depth 4603 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Company License Number 9087

Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 1:30 p.m. Day: 22 Month: 11 Year: 19 87

Plugging proposal received from John Wise

(company name) R & C Drilling Company (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1173'

1st plug at 1170' with 50 sx cement, 2nd plug at 630' with 40 sx cement,

3rd plug at 420' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 p.m. Day: 22 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement,

2nd plug at 630' with 40 sx cement,

3rd plug at 420' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Howco. (If additional description is necessary, use BACK of this form.)

If (next did not) observe this plugging.

INVOICED

Signed Steve Durrant (TECHNICIAN)

DATE 12-2-87

INV. NO. 19023 11-22

11-25-87
STATE CORPORATION COMMISSION
NOV 25 1987
CONSERVATION DIVISION
WICHITA, KANSAS

