

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20741-00-00
Spot: SESENE Sec/Twnshp/Rge: 22-12S-21W
2964 feet from S Section Line, 217 feet from E Section Line
Lease Name: KING Well #: 1
County: TREGO Total Vertical Depth: 4210 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4210		300 sx
SURF	8.625	305		180 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2016 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix 4% gel cement w/300 # hulls and 900 # gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2016 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 2150', 1700', 925' and 305'. Ran tubing to 3280' and pumped 600 # of gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2150' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1100' and pumped 90 sx cement. Circulated cement out backside. Pumped 75 sx cement in braden head and cement started to circulate. POOH. Hooked to casing and pumped 85 sx cement. Cement circulated out of braden head. Shut in pressure 300 psi.

GPS: 38.99471 -099.63258

Perfs:

KCC WICHITA
JAN 24 2017
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6127 ANGLE FEE FUND PROJECT CONTROL # 2017006-001

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

C.M.

JAN 12 2016

Form CP-2/3