

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20839-00-00
Spot: NESENE Sec/Twnshp/Rge: 22-12S-21W
3627 feet from S Section Line, 218 feet from E Section Line
Lease Name: KING Well #: 2
County: TREGO Total Vertical Depth: 3974 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3966		250 sx
SURF	8.625	329		180 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KANSAS CORPORATION COMMIS Phone: (620) 727-3410

Proposed Plugging Method: Ordered 700 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Can't drill past hard Iron at 2047'. Will plug at this depth per district supervisor.
DV Tool at 1670' w/500 sx cement.
Perforations: 3862' - 3876' and 3955' - 3974'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2017 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2047' and pumped 306 sx cement. Pulled tubing to 1100' and pumped 315 sx cement w/600 # hulls. Well on slight vacuum. Pulled tubing out.
01/10/2017 - Ran tubing back in and tagged cement at 692'. Pumped 84 sx cement. Good circulation of cement. Pulled tubing and topped off casing with 15 sx cement. Tied on to backside and squeezed without cement with 1200 psi.

GPS: 38.99624 -099.63252

Perfs:

KCC WICHITA
JAN 24 2017
RECEIVED

Remarks: QUALITY CEMENT TICKET # 6128 ANGLE FEE FUND PROJECT CONTROL # 20170006-002

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CR

JAN 12 2016