

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20923-00-00
Spot: SWNE Sec/Twnshp/Rge: 22-12S-21W
4295 feet from S Section Line, 878 feet from W Section Line
Lease Name: KING Well #: 4
County: TREGO Total Vertical Depth: 4073 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4073		175 sx
SURF	8.625	340		240 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2017 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement, 400 # hulls and 900 # (9 sx) gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2017 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

01/27/2017 - Rigged up and ran bailer in well. Stacked out at 2200'.
01/30/2017 - Perforated at 2150', 1725', 950' and 340'. Ran tubing in and hit solid at 2200'.
Pulled one joint of tubing and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1100' and pumped 120 sx cement. Circulated cement out of backside into pit. POOH. Hooked to casing and pumped 115 sx cement. Circulated cement out the braden head. Shut in and pumped 15 sx cement at 375 psi. Shut in.

GPS: 38.99767 -099.63487


KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6130 ANGLE FEE FUND PROJECT CONTROL #
20170006-004

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

FEB 02 2017