

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-20953-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 22-12S-21W  
3625 feet from S Section Line, 1536 feet from E Section Line  
Lease Name: KING Well #: 5  
County: TREGO Total Vertical Depth: 3980 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 266 N MAIN ST, STE 220  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3960		150 sx
SURF	8.625	351		200 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2017 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3410

Proposed Plugging Method: Well was drilled in 03/01/1982. Operator attempted to cement top stage of casing, set a RBP at 3300' and perforated the 4 1/2" casing at 1020'. Pumped 350 sx cement and cement circulated. After completing the top stage they found the 4 1/2" casing had collapsed at 870'. Several attempts made with no success and they abandoned the well. Operator drilled a replacement well # 7.  
Ordered 200 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2017 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Unable to get below 913'. Ran tubing to 913' and pumped 65 sx cement. Good circulation of cement. Pulled tubing out. Topped off with 10 sx cement. Tied on to casing and squeezed with 10 sx cement. Shut in pressure 1300 psi. Backside is full of cement.

GPS: 38.99632 -099.63723

Perfs:

KCC WICHITA  
FEB 14 2017  
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6130 ANGLE FEE FUND PROJECT CONTROL  
#20170006-005

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

JAN 31 2017

Form CP-2/3