

9-19

2-100633

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-079-20,228-0000

S/2 SW NW, SECTION 25 TOWNSHIP 22 RANGE 3W

OPERATOR LICENSE # 5526 FEET FROM S SECTION LINE \_\_\_\_\_  
FEET FROM E SECTION LINE \_\_\_\_\_

OPERATOR Harold Milburn  
NAME & 7315 N. Monroe  
ADDRESS Hutchinson, KS 67502

LEASE NAME: Randall #1  
COUNTY: Harvey 105.95  
WELL TOTAL DEPTH: 3260' PB 3238'

PIPE: 4-1/2" @ 3252'/75 sx  
SURFACE CASING: 8-5/8" @ 180'/150 sx

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: perf 3160' - 3211'

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Box 147, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 2:30 DAY: 19 MONTH: 9 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Ronnie Hoover  
COMPANY NAME: Kelso Casing Pulling PHONE: \_\_\_\_\_

WERE: Sand 50' above perms - 4 sx - pull casing to 350' - circulate.

PLUGGING PROPOSAL RECEIVED BY: Doug Louis

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 5:00p DAY: 19 MONTH: 9 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Sand to 3100' & dump 4 sx cmt - shot & pulled 1712' of 4-1/2" to 350' - pumped 2 sx hulls, 120 sx cmt - did not circ & gas blew out cmt - pulled 4-1/2" - hooked up swedge & pumped 3 sx hulls & 150 sx cmt from top - shut-in well.

REMARKS: Howco #015700 60/40 2% gel

I DID OBSERVE THIS PLUGGING.

**INVOICED**

OCT 05 1990

DATE \_\_\_\_\_

INV. NO. 29547

John Sanders  
John Sanders (AGENT)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
OCT 9 1990

10-1-90

FORM CP-2/3  
REV. 3/90