

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

6/88

API NUMBER 15-083-21,129-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Landmark Oil Exploration, Inc. OPERATORS LICENSE NO. 6133-6113

ADDRESS 110 S. Main, #510 Wichita, KS 67202 PHONE # (316) 265-8181

LEASE (FARM) Mennonite Church WELL NO. 1-24 WELL LOCATION NW SW NE COUNTY Hodgeman

SEC. 24 TWP. 22S RGE. 23 OIL (W) TOTAL DEPTH 4629 PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 259' CEMENTED WITH 175

CASING SIZE 4 1/2 SET AT 4629' CEMENTED WITH 125

PERFORATED AT 4580-90; 4361-65

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE 5-10-88

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mix 2sks cottonseed hulls w/ water & pmp

down casing. Follow w/ 180 sks HLC containing 2% Econolite & 1 sack cottonseed hulls. Fill

4 1/2" casing & 8 5/8" sfc. csg. to surface or cellar w/ cement blend. 50 sks HLC w/ 2% Econolite-

(If additional space is needed use back of form) _____ extra if necessary.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes
(If not, explain) with ACO-1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 18, 1988 Morning hours

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. Don Noland c/o Halliburton Services PHONE # (913) 798-2435

ADDRESS Box 405 Ness City, KS 67560

PLUGGING CONTRACTOR _____ LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: May 9, 1988

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1988
SACKS
CONSERVATION DIVISION
Wichita, Kansas

①

State of Kansas



15-083-21129-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

May 11, 1988

WG 11 '88

WELL PLUGGING NOTICE

EXPIRES

Mennonite Church #1-24
NW SW NE
Sec. 24-22S-23W
Hodgeman County

Landmark Oil Exploration, Inc.
110 S. Main, Ste. 510
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist in cursive script.

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760