



Phone: 316-337-6200
Fax: 316-337-6211
<http://kcc.ks.gov/>

Jay Scott Emler, Chair
Shari Feist Albrecht, Commissioner
Pat Apple, Commissioner

Corporation Commission

Sam Brownback, Governor

January 06, 2017

01/07/2017

Dan A Nixon
R. P. Nixon Operations, Inc
207 W 12TH
HAYS KS 67601-3810

KCC WICHITA License No. 5252
JAN 12 2017
RECEIVED

REQUEST FOR INFORMATION

Re: API No. 15-051-23483-00-01
Well Name: DOERR 3
NWNESE, 34-15S-19W
ELLIS County, Kansas

Operator:

Commission records indicate that the APRIL 14, 1992 Intent to Drill on the above-referenced well has expired. Staff has not received a spud call or a Well Completion Report ("ACO-1") for this well.

Please indicate below whether the well was drilled, by check-marking one of the two boxes below.

This well WAS drilled: ☒

This well WAS NOT drilled:

Please sign and date this letter, and return it to the Commission at the address listed at the top of this page.

Signature: 

Date: 1/10/17

Pursuant to K.A.R. 82-3-128, failure to verify requested information shall be punishable by a \$100 penalty.

**Failure to complete and return this letter
by JANUARY 20, 2017
shall be punishable by a \$100 per-well administrative penalty.**

Please contact me at (316) 337-6200 if you have any questions.

Sincerely,

KAREN J. RITTER
Production Department

KCC WICHITA

JAN 12 2017

RECEIVED

CITY OF HAYS
HAYS KS 67601

34-15 -19W
NW NE SE

#3 DOERR OWWO

DST (3) 3360-3420 (LKC), / 45-30-45-30, REC 300' GSY WTRY M, IFP PLUGGED ISIP 1124#
FSIP 1037# -143# FFP 121# -187#

NO CORES

MICT - CO, PF (LKC) 1/3558, 1/3530, 1/3509, AC 6000 GAL (28%), SWB DWN, GSO & G, PF
(LKC) 1/3483, 1/3345, 1/3323, AC 6000 GAL (28%), SWB DWN, GSO, POP, P (EST) 25 BOPD &
TR WTR, 9/1/83

NEW INFO: FR 04/14/92, RE-ENTERED 04/13/92 WSH DWN TO 414, LOGGED, LTD 416, DC
04/14/92 CSG: SURF CSG IN HOLE TRGT ZN: DAK SD, PTD 350 (DAK SD), MICT - CO, PF (DAK
SD) 7/364-372, SWB DWN, PF (DAK SD) 14/216-230, SWB DWN, WELL DRLO AS WTR TST HOLE,
DECISION MADE TO P & A (4/92)

CITY OF HAYS
HAYS KS 67601

34-15 -19W
NW NE SE

#3 DOERR OWWO

site: 1/2 S & 4-1/4 W OF SCHOENCHEN KS

city: ELLIS

API 15-051-23483-A

contr: R P NIXON

field: ZIMM

geol:

fr date 04/14/92 spd date 04/13/92 drlg comp 04/14/92 card issued 05/11/92 test revised 05/11/92

ELV: 2037 KB, 2032 GL LOG
tops.....depth/datum
ANH.....1236 +801
HEEB.....3268 -1231
LANS.....3320 -1283
BKC.....3562 -1525
RTD OLD.....3654 -1617

IP status:

D&A, PENN,

NOTE: KCC API 15-051-23483-0001

OLD INFO: OPERATOR WAS EURAM PETROLEUM, 3
DOERR, SPD 05/31/83, 06/07/83 8 5/8" 507/385; 5 1/2"
3653 (ALT 1), OIL, P 25 BOPD & TR W, LKC 3323-3558
OA, (CARD ISSUED 09/01/83)

CONTR: REVLIN DRILLING

DST (1) 3192-3254 (SHAW), / 45-30-45-30, REC 170'
GSY M, W/TR OIL, IFP PLUGGED ISIP 1048# FSIP
1015# -99# FFP 88# -121#

DST (2) 3306-3351 (SHAW, LKC), / 45-30-45-30, 240'
GIP, REC 120' OIL & GCM (20% OIL) ISIP 441# FSIP
374# IFP 44# -66# FFP 55# -77#

COPYRIGHT 1992
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

R. P. Nixon Operations, Inc.

Dan A. Nixon
President

207 West 12th Street Hays, Kansas 67601
785-628-3834 FAX 785-628-2356

January 11, 2017

KCC WICHITA

Karen J. Ritter
266 N. Main St., Ste.220
Wichita, Ks 67202-1513

JAN 12 2017

RECEIVED


Karen:

Please find enclosed the scout card for the well, Doerr #3. This well was re-entered on 4/13/92 and was a wash down to the Dakota Sand. After testing the hole, the Doerr #3 the well was plugged and abandoned. This is the only information we can collect.

If you have any more questions in regards to this well you can contact me at 785-628-3834.

Sincerely ,

R.P. Nixon Operations, Inc.



Sean A. Nixon, Vice President