

Conservation Division
266 N. Main St., Ste. 220
Wichita, KS 67202-1513



Phone: 316-337-6200
Fax: 316-337-6211
<http://kcc.ks.gov/>

Jay Scott Emler, Chair
Shari Feist Albrecht, Commissioner
Pat Apple, Commissioner

Corporation Commission

Sam Brownback, Governor

January 06, 2017

KCC WICHITA

JAN 10 2017

RECEIVED

License No. 5003

McCoy Petroleum Corporation
McCoy Petroleum Corporation
9342 E CENTRAL
WICHITA KS 67206-2573

REQUEST FOR INFORMATION

Re: API No. 15-189-22181-00-00
Well Name: DAVIS B 1-24
SESWNE, 24-32S-35W
STEVENS County, Kansas

Operator:

Commission records indicate that the MAY 16, 1997 Intent to Drill on the above-referenced well has expired. Staff has not received a spud call or a Well Completion Report ("ACO-1") for this well.

Please indicate below whether the well was drilled, by check-marking one of the two boxes below.

This well WAS drilled: D+A 12/29/1997

This well WAS NOT drilled:

Please sign and date this letter, and return it to the Commission at the address listed at the top of this page.

Signature: Brent B Reinhardt

Date: 1/9/2017

Pursuant to K.A.R. 82-3-128, failure to verify requested information shall be punishable by a \$100 penalty.

**Failure to complete and return this letter
by JANUARY 20, 2017
shall be punishable by a \$100 per-well administrative penalty.**

Please contact me at (316) 337-6200 if you have any questions.

Sincerely,

KAREN J. RITTER
Production Department

replacement card

MCCOY PETROLEUM CORP
WICHITA KS 67226-4003

24-32S-35W
2970' FSL & 1650' FEL, SEC (IRREG)

#1-24 DAVIS B

site: 5 S & 7 E OF MOSCOW KS city: STEVENS API 15-189-22267
 contr: SWEETMAN DRILLING #2 field: LARRABEE
 geol: COREY N BAKER

fr date 11/21/1997 spd date 12/12/1997 drlg comp 12/29/1997 card issued 01/19/1998 last revised 04/16/2001

ELV: 2985 KB, 2976 GL SMP

tops	depth/datum
HEEB	4199 -1214
LANS	4277 -1292
STARK	4803 -1818
HUSH	4878 -1893
MARM	4994 -2009
CHEM SH	5199 -2214
MRW SH	5624 -2639
CHEST LM	5951 -2966
CHEST SD UPR	6056 -3071
B/CHEST SD UPR	6060 -3075
CHEST SD LWR	6096 -3111
B/CHEST SD LWR	6126 -3141
STE GEN	6149 -3164

IP status

D&A, MISS, 12/29/1997

RTD.....6200 -3215

LTD.....6204 -3219

LOGGED

INFO RELEASED: 4/16/2001 - WAS D & A - TIGHT HOLE

CSG: 8-5/8" 1762 (ALT 1)

COMMENT: WAS ABD LOC, EXPIRED PERMIT (FR 5/16/1997, OPER: SAME, API 15-189-22181)

DST (1) 5594-5673 (MRW), / 30-60-60-120, (1ST OP) 1/4 INCH BLO BLT TO 1 INCH IN BKT, (2ND OP) NB, REC 30' M, NS ISIP 60# FSIP 70# IFP 33# -40# FFP 41# -44# IHP 2687# FHP 2695# BHT 131'

COPYRIGHT 2001
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

MCCOY PETROLEUM CORP
WICHITA KS 67226-4003

24-32S-35W
SE SW NE

#1-24 DAVIS B

site: 5 S & 7 E OF MOSCOW KS city: STEVENS API 15-189-22181
 contr: SWEETMAN DRILLING field: LARRABEE

fr date 05/16/97 spd date drlg comp card issued 12/01/97 last revised 12/01/97

ELV: 2985 EGL

IP status

ABD LOC, 12/01/97

CSG: SP 600 (ALT 1)

COMMENT: DUPLICATE FILING - REPLACED BY #1-24 DAVIS B (FR 11/21/97, API 15-189-22267)

TRGT ZN: MRW, CHEST (OIL/GAS), PTD 6300 (MISS), EXPIRED PERMIT

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

KCC WICHITA

JAN 10 2017

RECEIVED