

RECEIVED  
FEB 14 2002  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-055-20071 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR GMX Resources, Inc. KCC LICENSE # 32281  
(owner/company name) (operator's)

ADDRESS 9400 N. Broadway, Ste. 600 CITY Oklahoma City

STATE OK ZIP CODE 73114 CONTACT PHONE # (405) 600-0711

LEASE Stevenson WELL# 1 SEC. 6 T. 22S R. 33 (East/West)

C - NE - NE SPOT LOCATION/0000 COUNTY Finney

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE N/A SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 401' CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4779' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Miss - 4719-4724'

ELEVATION 2902' KB T.D. 4780 PSTD 4740± ANHYDRITE DEPTH 1950'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run tubing and packer, isolate leak, set CIBP at 4500' with 2 sacks cement, if casing leak is below 1150', set CIBP at 1150', perforations at 1100', cement with 180 sacks cement, pump 80 sacks outside casing, if cement does not circulate, pump 150 sacks down surface casing  
(If additional space is needed attach separate page)  
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? No logs available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Keith Hill, Crown Consulting, Inc. PHONE# (620) 624-0156

ADDRESS PO Box 1816 City/State Liberal, KS 67905-1816

PLUGGING CONTRACTOR unknown at this time KCC LICENSE # 99999  
(company name) (contractor's)

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 2-18-02

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-13-02 AUTHORIZED OPERATOR/AGENT: \_\_\_\_\_  
(signature)