

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

SEP 22 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-079-20,388-0000

C S2 SE, SECTION 23 TOWNSHIP 22 RANGE 3W

OPERATOR LICENSE # 4419 660 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR BEAR PETROLEUM INC
NAME & BOX 438
ADDRESS HAYSVILLE, KS 67060

LEASE NAME: STRUEBY #1 105.46
COUNTY: HARVEY
WELL TOTAL DEPTH: 3245' (3235')

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 206'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: GRESSEL OILFIELD SERVICES INC
ADDRESS: BOX 607, BURRTON KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 1145 DAY: 30 MONTH: 8 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: R A SCHREMMER
COMPANY NAME: BEAR PETROLEUM INC PHONE: 316-524-1225

WERE: SAND TO 3120' - CAP WITH 4 SX CMT - SHOOT PIPE OFF &
PULL SAME - RUN TUBING TO 260' & CIRC CMT TO SURFACE
4-1/2" CSG @ 3241'
PERFS 3168' TO 3196'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

COMPLETED: HOUR: 15:30 DAY: 30 MONTH: 8 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED TO 3000' & TOPPED W/4 SX CMT - SHOT PIPE OFF @
510' & PULLED SAME - RAN TUB TO 260' & CIRC 153 SX CMT
TO SURF - RECHECKED TOP PLUG 9/13 - CMT @ SURF - O.K.
RETRIEVED 510' OF 4-1/2" CASING

REMARKS: USED 60/40 POZ 4% GEL BY SUN #4473

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

Michael R. Wilson
Michael R. Wilson (AGENT)

DATE 9-23-94
INV. NO. 41246