

1 120126

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 2/14/63

C SE NE, SEC. 20, T 22 S, R 22 W/E

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Bamberger Well # 5

Operator: Berexco Inc.

County Hodgeman

Name & Address Box 723

Well Total Depth 4472 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Berexco Inc. License Number 5363

Address Box 723, Hays, KS 67601

Company to plug at: Hour: 10 a.m. Day: 17 Month: 8 Year: 19 88

Plugging proposal received from George Jorganson

(company name) Berexco Inc. (phone) 913-628-6101

were: 5 1/2" at 4459' Perfs at 4238-46'

1st plug sand back to 4190' with 5 sx cement on top of sand through bailer,
2nd plug load hole with mud and shoot at 800' with 300 sx cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 17 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CTBP at 4406', sanded back to 4190' and dumped 5 sx
cement on top of sand through bailer,

2nd plug pumped into 5 1/2" casing with 150 sx cement, didn't circulate, pumped 120 sx
cement in 8 5/8" X 5 1/2" annulus.

3rd plug pumped an additional 30 sx cement in 5 1/2",

8 5/8" - pumping pressure 0-400 psi and shut in 100 psi. 5 1/2" pumping 0-500 psi and shut in
200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 8-24-88

Signed [Signature]
(TECHNICIAN)

INV. NO. 21902

8-17 NOV 15 1988