

To: 1 051777 1-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

Docket  
E-13,232  
API NUMBER 15- 15-083-10304-0001  
C SE NW, SEC. 20, T 22 S, R 22 1/4  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5363  
Operator: BEREXCO, Inc.  
Name & Address P.O. Box 723  
Hays, KS 67601

Lease Name Bamberger Well # 11  
County Hodgeman 147.88  
Well Total Depth 4550 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied License Number \_\_\_\_\_  
Address P.O. Box 31, Russell, KS 67665-0031

Company to plug at: Hour: 11 a.m. Day: 21 Month: 1 Year: 19 94

Plugging proposal received from Bob Grant  
(company name) BEREXCO, INC. (phone) 913-628-6101

logs: 5 1/2" at 4528' w/100 sx cement, CIRP 4450', Perfs at 4503, 4494-4500'  
1st plug run tubing to 4424' with 100 sx cement,  
2nd plug at 2967' with 100 sx cement, 3rd plug at 1529', circulate to surface with 110 sx cement,  
4th plug pump down 5 1/2" with 80 sx cement,  
5th plug pump down 8 5/8" X 5 1/2" with 150 sx cement.

1-26-94  
STATE CORPORATION COMMISSION  
RECEIVED  
JAN 26 1994  
CONSERVATION DIVISION  
Wichita, Kansas  
Durrant  
(TECHNICIAN)

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 21 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug run tubing to 4424' with 100 sx cement,  
Pumped through tubing:  
2nd plug at 2967' with 100 sx cement,  
3rd plug at 1529' <sup>250' perf.</sup>, circulate to surface with 110 sx cement,  
4th plug pumped down 5 1/2" casing with 80 sx cement, Maximum pressure 100 psi and shut in 100 psi.  
5th plug pumped down 8 5/8" X 5 1/2" annulus with 150 sx cement. Maximum pressure 500 psi and  
shut in 200 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. Recovered no casing.

Additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

INVOICED  
DATE FEB 02 1994  
WEL. NO. 39842

Signed Richard W. Lacey  
(TECHNICIAN)