

1090315

8-27

15-083-10196-0001 Docket #D-13,446

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 19, T. 22 S, R. 22 W
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company
Name & Address: 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Miller Well # 1 SWD
County Hodgeman 151.93
Well Total Depth 4675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 27 Month: 8 Year: 19 93

Plugging proposal received from Ed Mondero
(company name) Pickrell Drilling Company (phone) 316-262-8427

work: 5 1/2" at 4659' w/100 sx cement, PBTD 1065', Perfs at 975-995', Squeezed at 1484' w/350 sx cement
1st plug set CIBP at 1065', TOC 100'

2nd plug run tubing to 980' and circulate cement to surface.

Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 27 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1065',

2nd plug tried to pump into perfs at 975', pressured to 600 psi-would not take. Ran tubing to 980' and circulated 90 sx cement to surface.

Hooked onto backside-would not take cement. 8-31-93

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form) AUG 31 1993

INVOICED
DATE 9-9-93
INV. NO. 38577
8-27

Signed [Signature] (TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

OCT 28 1993