

To: 1051643 4-26
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Operator: Pintail Petroleum Ltd.

Name & 225 N. 1st St.
Address 412 E. Douglas, Ste. One Suite 300
Wichita, KS 67202

API NUMBER 15- 083-21,393-0000

NE SE, SEC. 11, 'T' 22 S, R 22 W/E

1980 feet from S section line.

660 feet from E section line

Lease Name Bauer Well # 1

County Hodgeman 144.13

Well Total Depth 4435 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard J.V. License Number 4958

Address P.O. Box 905, McPherson, KS 67460

Company to plug at: Hour: Day: 26 Month: 4 Year: 1993

Plugging proposal received from Pam

(company name) Mallard J.V. (phone) 316-241-4640

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1336-65'

1st plug at 1360' with 50 sx cement, 2nd plug at 600' with 80 sx cement,

3rd plug at 220' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 p.m. Day: 26 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 1360' with 50 sx cement,

2nd plug at 600' with 80 sx cement,

3rd plug at 220' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

1 (xxx) / did not observe this plugging.

DATE 5-4-93

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 37645 JUL 22 1993

4-26 JUN 20 1993

RECEIVED
STATE CORPORATION COMMISSION

MAY - 4 1993

CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 3-22-93DISTRICT # 1SSAT Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL 083-21,393-0000

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 4 1 93
month day yearSpot NE SE East
Sec 11 Twp 22 S. Rg 22 XX WestOPERATOR: License # 5086
Name: Pintail Petroleum Ltd.
Address: 412 E. Douglas # 1
City/State/Zip: Wichita, KS. 67202
Contact Person: Innes Phillips
Phone: (316) 263-2243CONTRACTOR: License # 4958
Name: Mallard JV

Well Drilled For: Well Class: Type Equipment:

☒ Oil ☒ Enh Rec ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Storage ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Disposal ☒ Wildcat ☐ Cable
☐ Seismic: ☐ # of Holes ☐ Other

If OWWO: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth Directional, Deviated or Horizontal wellbore? yes X noIf yes, true vertical depth: Bottom Hole Location:

Exp. 9/22/93

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the following

Pusher Pam
 SPUD DATE 4-19-93 INIT. SM
 LENGTH SURFACE PLANNED 210
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 8 3/4 @ 1982.5 CONDUCTOR
 ANHYDRITE T- 1324 B- 1365 ELEVATION
 TD 4435 FORMATION
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
 Arbuckle Plug @ Ft. W/ SX
 Hug./Council @ Ft. W/ SX
 Anhydrite Base @ 1360 Ft. W/ 50 SX
 1/2 Base Anyh. @ 600 Ft. W/ 80 SX
 1/2, 1/2 Plug @ Ft. W/ SX
 Bottom Surface @ 220 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
 WATER WELL SX (Irr. Well Pond)
 TECHNICIAN R.L. DATE 4-26-93 Hauling
 TYPE OF CEMENT 60/40 po2 6% gel 1/4 Flowstat
 STARTING TIME 7:30 (AM/PM) DATE 4-26-93
 COMPLETION TIME 1:30 (AM/PM) DATE 4-26-93
 CEMENT COMPANY Hall

393