

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10243-00-00
Spot: CNESW / Sec/Twnshp/Rge: 7-22S-22W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 6
County: HODGEMAN Total Vertical Depth: 4615 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: \$149.99
Surface Casing: Size 8.625 feet: 269
Production: Size 5.5 feet: 4597 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/13/2002 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS TO BOTTOM. PRESSURE TEST. PERFORATE AT 550' & PUMP 150 SX CMT. PRESSURE TEST. TIE ONTO BACKSIDE AND PUMP 150 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/13/2002 2:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4552'. PERFS AT 4533-35'. PUMPED 35 SX CMT & 200# HULLS TO BOTTOM. PRESSURED TO 1100#. PERFORATED AT 550' & PUMPED 150 SX CMT. MAXIMUM PRESSURE 1500#. SHUT IN WITH 700#. TIED ONTO BACKSIDE AND PUMPED 150 SX CMT. MAXIMUM PRESSURE 450#. SHUT IN WITH 300#.

RECEIVED

MAY 17 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael J. Maier
(TECHNICIAN)

INVOICED
DATE 5-20-02
INV. NO. 2002061791

MAY 14 2002



