

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21037-00-01
Spot: CNENW Sec/Twnshp/Rge: 35-22S-22W
660 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: CLELAND Well Number: 1
County: HODGEMAN Total Vertical Depth: 4440 feet

Operator License No.: 5363

Conductor Pipe: Size feet:

Op Name: BEREXCO, INC.

Surface Casing: Size 8.625 feet: 306 WITH 200 SX CMT

Address: 100 N. BROADWAY, STE. 970
WICHITA, KS 67202

Production: Size 4.5 feet: 4434 WITH 100 SX CMT

Liner: Size feet:

14430

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/03/2001 12:05 PM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO

Phone: (785) 628-6101

Proposed Plugging Method: PUMP 300# HULLS & FILL 4 1/2" WITH 60/40 POZMIX 6% GEL. PUMP 100 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/03/2001 2:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE 4434-4440'. SQUEEZED AT 1040-43' WITH 350 SX CMT & 50 SX COMMON CMT. PUMP 200# HULLS WITH FIRST BATCH OF CMT. PUMPED 15 BBL WATER DOWN CASING TO SEE IF WE COULD PUMP INTO FORMATION. INJECTION RATE OF 4 BBL A MINUTE AT 150#. THEN MIXED 260 SX CMT. MAXIMUM PRESSURE 2500#. SHUT IN WITH 1000#. TIED ONTO BACKSIDE AND PUMPED 10 SX CMT. PRESSURED TO 500# AND HELD.

1-19-01

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 19 2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CONSERVATION DIVISION

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

INVOICED

DATE 1/22/01
INV. NO. 2001061343

JAN 09 2001

Form CP-2/3

MP