

1 030145

15-185-30096-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. March 28, 1965

SW NW NE, SEC. 36, T 22 S, R 14

feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Staub Well # 1

Operator: Graves Drilling Co., Inc.

County Stafford

Name & Address 910 Union Center,

Well Total Depth 3839 124.77 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 30 Month: March Year: 19 84

Plugging proposal received from Gene Smith

(company name) Kelso (phone) 316-938-2457

were: 5 1/2 set at 3687 Perfs 3583

1st plug sand to 3530 and dump 5 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls
and release 8 5/8" rubber plug and pump additional 100 sx cement

Maximum pressure 500# and shut-in pressure 200#

Plugging Proposal Received by Steve Dement (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 am Day: 30 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3687 Perfs 3583

1st plug sand to 3530 and dump 5 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls
and release 8 5/8" rubber plug and pump additional 100 sx cement

Maximum pressure 500# and shut-in pressure 200#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 2095' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 4-4-84

APR 03 1984

Signed Steve Dement (TECHNICIAN)

INV. NO. 1049 3-30

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84