

5 030380.

6-16-88

144 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-079-20276-0000
SE NW SW, SEC. 26, T 22 S, R 3 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419

Operator: Bear Petroleum

Name & Address Box 243

Derby, KS 67037

4290 feet from ES section line

1650 feet from SE section line

Lease Name Schrag Well # 1

County Harvey 105.17

Well Total Depth 3236 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 200

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Ed Gressel Oil Field Service License Number 3004

Address Burrton, KS

Company to plug at: Hour: AM Day: 3 Month: 6 Year: 19 88

Plugging proposal received from _____

(company name) Gressel (phone) _____

were: 4 1/2" @3236 w/100 sxs Perf @3181 1/2 3176 1/2 3202'-08 Dump

sand to 50' above perfs and cap with 5 sxs cement by bailer. Shoot

pipe and recover. Build bridge @265'-250'. Dry hole, fill with redimix

to surface.

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part Top None _____

Operations Completed: Hour: 14:25 Day: 16 Month: 6 Year: 1988

ACTUAL PLUGGING REPORT Sand to 3115' and capped with 5 sxs cement. Shot pipe and

recovered 1010' of 4 1/2" casing. Bailed hole down 265' Bridged hole to

253' and filled with 6 1/2 yards redimix to surface.

STATE CORPORATION COMMISSION

JUN 21 1988 6-21-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: McPherson Concrete Products

(If additional description is necessary, use BACK of this form.)

INVOLCED

(If possible, observe this plugging.)

DATE 7-13-88

Signed Merle L. Lumb
(TECHNICIAN)

INV. NO. 21296

AUG 3 1988