

5 030528

10-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-079-20,192-0000

NE , SEC. 26, T 22 S, R 3 W/E

2970 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3202

Lease Name Tillie Shcrag Well # 1-B

Operator: Sierra Drlg Co

County Harvey 107.09

Name & Address P.O. Box 782050

Well Total Depth 3295 feet

Wichita, KS 67278

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 182

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS

Company to plug at: Hour: PM Day: 2 Month: 10 Year: 1989

Plugging proposal received from Vernon Dunce

(company name) Kelso Casing Pulling (phone) 316 938-2457

were: Sand 50' above perfs cap w/5sx

5 1/2 @ 3293' w/100 sx Perfs 3151' - 3213'

OCT 20 1989

Wichita, Kansas

Plugging Proposal Received by Dist 2 Office

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part top None

Operations Completed: Hour: 11:45 Day: 5 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT Sand 50' above perfs capped with 5 sx cmt by bailer.

Shot pipe @ 2822' & recovered circ cmt @ apprx 640' - 35 sx

" " " " 325' - 50 sx

" " " " 90' to surface (3 joints)

Remarks: Allied Cmtg

(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

INVOICED


Signed Melba Lusk
(TECHNICIAN)

DATE 10-25-89 WC

INV. NO. 26243

DEC 15 1989

FEB 09 1990



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250
McPHERSON, KANSAS 67460

September 4, 1973

COMPANY: HAROLD J. MILBURN
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: SCHRAG B-1
LOCATION: SW SE NE, Sec. 26-22-3W,
Harvey County, Kansas
COMMENCED: AUGUST 26, 1973
COMPLETED: August 31, 1973
ELEVATION: 1425 K. B.

0	to	20	Clay
20	to	50	Sand
50	to	110	Shale
110	to	182	Blue Shale
182	to	545	Shale & Lime
545	to	1265	Lime
1265	to	1865	Lime & Shale
1865	to	2415	Shale & Lime
2415	to	2525	Lime
2525	to	2680	Shale & Lime
2680	to	2870	Lime
2870	to	3155	Lime & Shale
3155	to	3295	Mississippi
		3295	T. D.

Cut 12 1/4 inch hole to 182 ft. and run 184 ft. of used 8 5/8 inch casing, cemented with 125 sacks of cement. Plug down at 1:00 P. M., August 19, 1973. Cut off drilling line. August 26, 1973, drilled plug at 12:45 A. M. Cut 7 7/8 inch hole to 3295 ft. Run 3321 of 5 1/2 inch pipe, cemented with 50 sacks of cement at 3285', plug down at 2:00 P. M., August 31, 1973.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Schrag B-1, located on the SW SE NE, Sec. 26-22-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.


Charles D. Johnson, Secretary-Treasurer