

1030396

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,193-0000 *P*

SW SE     , SEC. 32, T 22 S, R 18 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Shumate Well # 1

Operator: Halliburton Oil Producing Co.

County Pawnee 146.58

Name & Address 2915 Classen Blvd.

Well Total Depth 4510 feet

Oklahoma City, OK 73106

Conductor Pipe: Size      feet

Surface Casing: Size 8 5/8 feet 432 ✓

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereinafter indicated     

Plugging Contractor Aldebaran Drilling Co. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 9:00 pm Day: 11 Month: April Year: 19 85

Plugging proposal received from Scott Mason

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1230' with 50 sx cement

2nd plug at 870' with 50 sx cement

3rd plug at 450' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plug water well from bottom to surface

Plugging Operations attended by Agent?: All      Part      None X

Operations Completed: Hour: 11:00 pm Day: 11 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1230' with 50 sx cement, 2nd plug at 870' with 50

sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

from bottom to top.

RECEIVED

APR 23 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOLVED

(If necessary, do not) observe this plugging.

DATE 5-2-85

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 7919