

To: 1 040802 11-11  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-20,744-0000  
NE NE NE, SEC. 23, T. 22 S, R. 18 W/E  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum Ltd.  
Name & Address 225 N. Market, Ste. 300  
Wichita, KS 67202

Lease Name Fitz-Roy Well # 1  
County Pawnee  
Well Total Depth 4330 140.73 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:45 p.m. Day: 11 Month: 11 Year: 1993

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4329' w/175 sx cement, PBTD 4224', Perfs at 4196-4204, 4188-96, 4168-76'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,

2nd plug perforate at 500' and circulate to surface.

(cement on outside of 5 1/2" from 4329-500', Permian at 400-450')

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 11 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand bridge through bailer, Casing had been shot at 2600' and at 500'. 4 1/2" X 8 5/8"

annulus had been squeezed to surface in the past. 2nd plug pumped down 4 1/2" casing with 125

sx cement. Maximum pressure 700 psi and shut in 100 psi. 3rd plug pumped down 4 1/2" X 8 5/8"

annulus with 150 sx cement. Maximum pressure 500 psi and shut in 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
11-17-93  
NOV 17 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

If additional description is necessary, use BACK of this INFORMATION DIVISION  
Wichita, Kansas

I (did / ~~did not~~) observe this plugging.

DATE

INV. NO.

NOV 23 1993  
39290

Signed

(TECHNICIAN)

Stephen J. Pfeiffer