

To: R 1 120857 11-5
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,256-0000
SW SW NE, SEC. 13, T 22 S, R 18 W
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086
Operator: Pintail Petroleum Ltd.
Name & Address 225 N. Market, Ste. 300
Wichita, KS 67202

Lease Name Strobel Well # 1
County Pawnee
Well Total Depth 4340 141.05 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 5 Month: 11 Year: 19 93

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4340' w/165 sx cement, PBD 4124', Perfs at 4114-22'

1st plug sand back to 4060' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 80 sx cement at 1200',

3rd plug pump 50 sx cement at 270',

4th plug pump 10 sx cement at 40'.

*11-16-93
Red 11-16-93
KCC*

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 5 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4060' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot 5 1/2" casing at 2235'. Laid down 5 1/2" to 1260' and pumped in 10 sx gel, laid down 5 1/2" to 1225' and pumped 50 sx cement. 3rd plug laid down 5 1/2" to 715' and pumped in 5 sx gel with hulls. Laid down 5 1/2" to 680' and pumped in 100 sx cement. 4th plug laid down 5 1/2" to 390' and circulated with 125 sx cement. 5th plug pulled all 5 1/2" and topped with 25 sx cement.

Remarks: Used 60/40 Pozmix 2% gel by Allied. Recovered 2235' of 5 1/2" casing.
(Additional description is necessary, use BACK of this form.)

INVOICED

DATE: NOV 23 1993 observe this plugging.

DIV. NO. 39287

Signed Steve Middleton
(TECHNICIAN)