

1030250

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,065-0000

SW SE NW, SEC. 29, T 22 S, R 13 W/K

2970 feet from ~~XXX~~ section line

3630 feet from ~~XXX~~ section line

VEATCH

Lease Name Spangenberg Well # 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

County Stafford

Operator: Oil Producers, Inc. of Kansas

Name & Address P. O. Box 8647

Well Total Depth 3890 126.43 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor D. R. Lauck Oil Co., Inc. License Number 5427

Address 221 South Broadway, Suite 400, Wichita, KS 67202

Company to plug at: Hour: 11:00 am Day: 15 Month: August Year: 1984

Plugging proposal received from Doyle Folkerts

(company name) D. R. Lauck (phone) 316-263-8267

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 800' with 50 sx cement

2nd plug at 390' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Steve Whinnant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 pm Day: 15 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement, 2nd plug at 390' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement and plugged water well with 5 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

8-24-1984

AUG 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form, Kansas

INVOICED observe this plugging.

DATE 8-27-84

Signed Steve Whinnant SD
(TECHNICIAN)

INV. NO. 3398