

To: 1 030702  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,446-0000

NE SE NW, SEC. 6, T 22 S, R 14 W/3  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Russell Well # 1 SWD

Operator: H-30 Drilling, Inc.

County Stafford 130.94

Name & Address 251 North Water, Suite 10

Well Total Depth 4029 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 575

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 pm Day: 10 Month: June Year: 1986

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3908' 4 1/2" liner set at 3000' cemented inside 5 1/2" to the top.

1st plug pump 4 sx hulls, 30 sx cement, 20 sx gel and 60 sx cement

2nd plug pump 100 sx cement down backside.

Plugging Proposal Received by Don C. Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 10 Month: June Year: 1986

ACTUAL PLUGGING REPORT Pumped 4 sx hulls, 30 sx cement, 20 sx gel, and 60 sx cement

Maximum pressure 750 psi and shut in 750 psi.

2nd plug pumped 100 sx cement down annulus 0 shut-in on Annulus

RECEIVED  
STATE CORPORATION COMMISSION

JUN 16 1986

6-16-86

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 18 1986

Signed Steve Shumout  
(TECHNICIAN)

INV. NO. 14132

6-10