

1030310

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,092-0000
NE NE NE, SEC. 14, T 22 S, R 13 W/~~E~~
N SE Corner of
4950 feet from ~~XXX~~ section line
W SE Corner of
330 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9180

Lease Name Hayden Well # 1

Operator: Wildcat Drilling Company

County Stafford

Name & Address 200 West Douglas, Suite 250

Well Total Depth 3826 ^(24.35) feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wildcat Drilling Company License Number 9180

Address 200 West Douglas, Suite 250, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 27 Month: October Year: 19 84

Plugging proposal received from Herb Boxberger

(company name) Dunne-Gardner (phone) 316-265-1611

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 780' with 50 sx cement

2nd plug at 300' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Almont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 pm Day: 27 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement, 2nd plug at 300' with 50 sx cement, 3rd plug & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1984

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 2% gel 3% cc
(if additional description is necessary, use BACK of this form.) 10-31-84

INVOICED (check/gls not) observe this plugging.

DATE 11-2-84

Signed Steve Almont
(TECHNICIAN)

INV. NO. 4628

10-27 DEC 07 1984