

1 070754

API NUMBER 15- 185-22,627-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW NE, SEC. 14, T. 22 S, R. 13 W/E

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name Fischer H Well # 1

Operator: Boger Brothers Drilling, Inc.

County Stafford 123.76

Name & Address P.O. Box 723

Well Total Depth 3808 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling, Inc. License Number 9421

Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 15 Month: 11 Year: 19 89

Plugging proposal received from Dick Smith

(company name) Boger Brothers Drilling, Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 746-760' Elevation 1885'

1st plug at 780' with 50 sx cement, 2nd plug at 330' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:35 a.m. Day: 15 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement,

2nd plug at 330' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement

RECEIVED

STATE CORPORATION COMMISSION

NOV 17 1989

11-17-89

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

INVOICED

(XXXX) did not observe this plugging.

DATE 11-20-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 26533

11-15

EFFECTIVE DATE: 11-11-89

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 185-22,627-0000 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. November 10, 1989 ..  
month day year

NW SW NE Sec 14 Twp 22 S, Rg 13 X East West

OPERATOR: License # 9421  
Name: Boger Brothers Drilling, Inc.  
Address: P.O. Box 723  
City/State/Zip: Great Bend, KS 67530  
Contact Person: Dale Smith  
Phone: 316-792-8151

3630 feet from South line of Section  
2310 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: Company Tools  
Name:

County: Stafford  
Lease Name: Fischer H Well #: 1  
Field Name: GATES

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj X Infield X Mud Rotary  
Gas Storage Pool Ext Air Rotary  
OAWD Disposal Wildcat Cable  
Seismic; # of Holes

Is this a Prorated Field? yes X no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: 1885 CL feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 140'  
Depth to bottom of usable water: 260'  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 350 280  
Length of Conductor pipe required: None  
Projected Total Depth: 3850  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
well farm pond X other

If OAWD: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

DWR Permit #: Will Cores Be Taken? yes X no

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location:

If yes, proposed zone:

Exp. 5/6/90

Set 280' of 95/8 on 11-9-89

280' Alt. I Req.

AFFIDAVIT

PUSHER Dick Smith  
TD 3808 FORMATION ABB  
SURFACE PIPE 8 5/8" @ 310'  
ANHYDRITE 746-760' ELEVATION 1885'  
STARTING TIME & DATE 9:00AM 11-15-89  
COMPLETION TIME & DATE 10:35AM 11-15-89  
1st PLUG @ 780 FT. W/ 50 SX  
2nd PLUG @ 330 FT. W/ 40 SX  
3rd PLUG @ 40 FT. W/ 10 SX  
4th PLUG @ FT. W/ SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ SX  
WATER WELL PLUGGED W/ SX  
CEMENT COMPANY Halliburton  
TECHNICIAN Dan  
TYPE OF CEMENT 60/40 6%

Arbu Top @ 40sx if  
Mile thru 50' into.

Vertical scale table with depth markings from 330 to 5280.

Spud date: Agent:

5280 4950 4620 4290 3960 3630 3300 2970 2640 2310 1980 1650 1320 990 660 330

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- Obtain appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.