

1070056

TO:

API NUMBER 15-185-21,684-0000

STATE CORPORATION COMMISSION

SW NW SW, SEC. 14, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION

1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME Hullman "C" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY Stafford 127.08

OPERATOR LICENSE # 32017

WELL TOTAL DEPTH 3910 FEET

OPERATOR: ABC Oil & Salvage

PRODUCTION CSG: SIZE 5 1/2" FEET 3906w/125 sx

NAME AND RR #3, Box 151

SURFACE CASING: SIZE 8 5/8" FEET 311

ADDRESS Lyons, KS 67554

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Quality Well Service, Inc. LICENSE NUMBER 31925

ADDRESS 249 Beth Dr., Sterling, KS

COMPANY TO PLUG AT: HOUR: 11:15 a.m. DAY: 6 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Richard McIntyre

(COMPANY NAME) Quality Well Service, Inc. (PHONE) 316-727-3410

WERE: Perfs at 3823-25', PBSD 3886'

1st plug sand back to 3775' and dump 5 sx cement on top of sand through bailer,

2nd plug at 900' w/10 sx gel and 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement.

PLUGGING PROPOSAL RECEIVED BY Richard Lacey

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:40 p.m. DAY: 6 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx Portland cement on top of sand through bailer,

2nd plug at 900' with 10 sx gel and 50 sx cement displaced with 5 sx gel,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement, circulated cement to surface.

REMARKS: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2420' of 5 1/2" casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

PLEASE PRESERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE FEB 17 1998

NO. 50078

2-6

STATE CORPORATION COMMISSION
FEB 18 1998
CONSERVATION DIVISION 2-13-98