

1 030414

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22,216-0000

SW NE NW, SEC. 20, T 22 S, R 13 W W&X  
4290 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Grimes A Well # 1

Operator: Grady Bolding Corporation  
Name & Address P. O. Box 244  
Great Bend, KS 67530

County Stafford  
(Arbuckle)  
Well Total Depth 3861 125-49 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address Box 308, Great Bend, KS 67530

Company to plug at: Hour: 3:00 pm Day: 11 Month: May Year: 19 85

Plugging proposal received from Richard Wheeler

(company name) Woodman - Iannitti (phone) 316-265-7650

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1902  
Anhydrite 770-793

1st plug at 775' with 50 sx cement

2nd plug at 330' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Clyde Wiley

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:15 am Day: 11 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 775' with 50 sx cement, 2nd plug at 330' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to  
circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

MAY 21 1985

5-21-85

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-21-85

Signed Steve DuMont  
(TECHNICIAN)

INV. NO. 8206

5-11