

To: 1 120071
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-17-88 109
API NUMBER 15- N/A 15-185-20158-0000
SW NE SE, SEC. 26, T. 22 S, R. 13 W/E
1650 feet from S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5673
Operator: W.L. Kirkman, Inc.
Name & Address P.O. Box 782290
Wichita, KS 67218-2290

990 feet from E section line
Lease Name Spaatz Well # 1
County Stafford 122.01
Well Total Depth 3754 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well Gas Well Input Well SHD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 17 Month: 2 Year: 19 88

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3747' Perfs at 3743-47'
1st plug sand back to 3680' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 3 p.m. Day: 17 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Pumping pressure 0-500 psi and shut in pressure 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2571' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (operator) observe this plugging.

DATE 2-29-88
INV. NO. 19932

Signed Duane Rankin (TECHNICIAN)