

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1971

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


Dear Sir:

Mr. Hallam of Cities Service has this

date requested permission to plug the following described well:

Mr. Hallam guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil CompanyComplete Address: Box 308, Great Bend, KansasLease Name: Hann "C" Well No. 1Location: C NE NW Sec. 27 Twp. 22 Rge. 22 ~~(E)~~ (W)County: Hodgoman Total Depth 4437' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Hallam was instructed to plug the well as follows:8 5/8" to 254' circulated w/ cement. 5 1/2" to 4427' cemented.Open hole from 4427' to 4437' Plug bottom w/ sand & 5 sacks cement.Top of cement 4300' Mud 4300' to 500'Spot 150 sacks cement 500' to 0'.

Very truly yours,



 Conservation Division Agent