

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sullivan of Pickrell has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bldg., Wichita, Kansas

Lease Name: Ruff "A" Well No. 1

Location: C SE NW Sec. 25 Twp. 22 Rge. 22 (E) (W)


County: Hodgeman Total Depth 4515' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

8 5/8" to 280' circulated w/ cement. 5 1/2" to 4506' cemented  
No perforations, 9' of open hole. Plug bottom w/ sand & 5 sacks cement  
Top of cement 4440' Mud 4440' to 850'  
Spot 80 sacks cement 850' to 550' Mud 850' to 550'  
Spot 30 sacks cement 280' to 180' Mud 280' to 40'  
Plug, Hulls & 10 sacks cement 40' to 0'..

Very truly yours,

  
Conservation Division Agent