



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

STATE RECEIVED
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sullivan of Pickrell has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bk., Bldg., Wichita, Kansas

Lease Name: Ruff "B" Well No. 1

Location: 150' NW C SW NE Sec. 25 Twp. 22 Rge. 22 (E)(W)

County: Hodgeman Total Depth 4530' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

8 5/8" to 277' circulated w/ cement. 5 1/2" to 4527' cemented.

Open hole 4527' to 4530' Plug, bottom w/ sand & 5 sacks cement.


Top of cement 4460' Mud 4460' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 270'

Spot 30 sacks cement 270' to 170' Mud 170' to 45'

Plug, H^ulls & 10 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent