



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

10-12-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reimert of Champlin has this

date requested permission to plug the following described well:

Mr. Reimert guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Co.

Complete Address: Box 308, Ellinwood, Kansas

Lease Name: Ruff Well No. 1

Location: C NE NE Sec. 25 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4495' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reimert was instructed to plug the well as follows:

8 5/8" to 251' circulated w/ cement. 4 1/2" to 4492' ciru. w/ cement.

No perforations- open hole 3'. Plug bottom w/ 15 sacks cement.

Top of cement 4200' Mud 4200' to 944'

Spot 15 sacks cement 944' to 760' Mud 760' to 50'

Plug, Halls & 5 sacks cement to 50' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent