



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-079-19114-0000

August 19, 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

AUG 31 1964

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Kantor Oil Company

Complete Address: 1720 First National Bldg., Tulsa, Oklahoma

Lease Name: Haury "B" Well No. 1

Location: C SE NE Sec. 11 Twp. 23 Rge. 2 (W) X

County Harvey Total Depth 2982' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 2960' and cement with 7 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to

150' and cement hole with 50 sacks. Fill hole with mud

to 35'. Set rock bridge from 35' to 25' and cap hole with

25 sacks cement.

Very truly yours,

Arthur J. Loman
 Conservation Division Agent