

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

August 15, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-155-30217-0001

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1969  
CONSERVATION DIVISION  
Wichita, Kansas

8-20-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Orr of Kathol Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Independent Lease Management Company

Complete Address: 800 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Johnson Well No. 1

Location: NE SE SW Sec. 32 Twp. 23 Rge. 10 (E) (W) X

County: Reno Total Depth 3819' Oil Well     

Gas Well      Input Well      SWD Well      Washdown  
D & A X Lost Hole     

Mr. Orr was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and  
cement hole with 30 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 15  
sacks cement.

Bridge rathole and cement with 2 sacks .

Very truly yours,

William J. Loman  
Conservation Division Agent