



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

August 30, 1972

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-155-20205-0000

9-6-72  
RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation

Complete Address: 200 W. Douglas, Suite 950, Wichita, Kansas

Lease Name: Zenith Unit (Johnson) Well No. 1-9

Location: NE NE NW Sec. 32 Twp. 23 Rge. 10 (E)(W)X

County: Reno Total Depth 3856' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud to 262'. Push Plug and 1/4 sack hulls to 262' and  
cement hole with 25 sacks cement through drill pipe at 262'. Fill  
hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole  
with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent