

15-185-20088-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 5, 1968.

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First National Bank Bldg., Wichita, Ks. 67202

Lease Name: Symns Well No. # 1

Location: C NW SE SE Sec. 36 Twp. 22 Rge. 14 (E)(W) W

County Stafford Total Depth 3872' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

352' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1968
Julie Elving
CONSERVATION DIVISION
Wichita, Kansas