

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Inc

Complete Address RT 2 Great Bend, KS

Lease Name Keller M Well No. 1

Location C E/2 NE Sec. 17 Twp. 22 Rge. 13 (E) (W)

County Stafford Total Depth 3831

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers Inc

Address Box 486 Ellinwood, KS License No. 462

Operation Completed: Hour 3:30 PM Day 21 Month 8 Year 1973

The above well was plugged as follows:

285 ft 8 5/8 surface cemented with 225 sacks. 3819 ft 5 1/2 long string  
cemented with 175 sacks. Open hole. Sand to 3780 ft, 5 sacks cement  
with bailer. Pulled 1960 ft 5 1/2. Pump 2 sacks hulls, 10 sacks gel,  
100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/24/73

INV. NO. 7811-W