



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 19-30

LOCATION SW-SW-2E

SEC. 36 TWP. 22 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Naet

Operator Mungrove Peter Corp Address 417 K.F.H. Bldg Wichita-Kans

Field _____ County Stafford

Total Depth 3832 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 325 ft. Circulated with cement.
5/8 casing set at 3829 ft - cemented with 100 sacks cement.
Plugged back to 3820 ft with chat - Dumped 4 sacks of
cement at 3820 ft - Ripped off & pulled the 5/8 casing.
Filled hole with sand to 325 ft - Set back Bridge &
20 sacks of cement at 325 ft - Mud to 30 ft Plug &
10 sacks of cement at the surface

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1951

CONSERVATION DIVISION
Wichita, Kansas

2-23-51

P. W. Stouck
District Conservation Agent

Date 2-21-51

PLUGGING
FILE SEC 36 TWP 22 RGE 14W
BOOK PAGE 59 LINE 30