

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Graves Drlg Co Inc

Complete Address 505 Union Center Wichita, KS

Lease Name Bartlett Well No. 2

Location C E/2 NE/NW Sec. 36 Twp. 22S Rge. 14 (E) (W) W

County Stafford Total Depth 3860

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 11:00 AM Day 21 Month 2 Year 1974

The above well was plugged as follows:

262 ft 8 5/8 surface cemented with 300 sacks. 3669 ft 5 1/2 long string  
cemented with 150 sacks. Top perf. 3597 ft. Sand to 3575 ft, 5 sacks  
cement with bailer. Pulled 2893 ft 5 1/2. Pump 2 sacks hulls, 20 sacks  
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/27/74  
INV. NO. 8634-W

Signed: [Signature]  
Well Plugging Supervisor