

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 67-22

LOCATION CSE-SE-21W

SEC. 36 TWP. 22 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Shiley Beaver

Operator Sinclair Oil & Gas Co Address Box #551 - Chase - Kans.

Field _____ County Stafford

Total Depth 3905 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/8 - 444 ft. Circulated with cement.
5 1/2 casing set at 3905 ft. Cemented with 175 sacks cement.
Cement Plug not drilled out after cementing 5 1/2 casing -
Casing Reperated at 3828 ft. Plugged back with chat to
3820 ft - Dumped 5 sacks cement at 3820 ft - Shot off &
pulled the 5 1/2 casing - mud to 250 ft - Set Rock Bridge
& 15 sacks of cement at 250 ft - Mud to 30 ft - Plug
& 10 sacks of cement at the surface -
Pipe Pulling, Inc. Plugging Contractor*

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 36 T 22 R 14W
BOOK PAGE 67 LINE 20

MAR 26 1951 District Conservation Agent
Wichita, Kansas Date 3-23-51

3-26-51