

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Bamberger Well No. 12

Location NE SW Sec. 20 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4535'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers Inc.

Address Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 3:00PM Day 28 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 260' circulated w/ cement. 5 1/2" to 4520' cemented.

Open hole 4535' to 4520' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4480' Mud 4480' to 850'

Spotted 80 sacks cement 850' to 550'. Mud 550' to 260'

Spotted 30 sacks cement 260' to 160' Mud 160' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Allied Pump Truck.

Pulled 3572' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: Edna J. Eves
Well Plugging Supervisor

DATE 7/2/74

INV. NO. 9445-W