

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden-Deem Inc
Complete Address 200 E 1st, Wichita, Kansas
Lease Name E. Oppy Well No. 1
Location SW NE Sec. 19 Twp. 22 Rge. 22 (E) (W)
County Hodgeman Total Depth 4631'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Chase, Kansas License No. 624
Operation Completed: Hour 1:00Pm Day 21 Month 2 Year 1973

The above well was plugged as follows:

8 5/8" to 257' circulated w/ cement. 5 1/2" to 4630' cemented.
Top perforations 4282' Plug bottom w/ sand & 5 sacks cement.
Top of cement 4200' Mud 4200' to 700'
Spotted 70 sacks cement 700' to 400' Mud 400' to 200'
Plug & 50 sacks cement 200' to 0'. Allied Pump Truck
Pulled 2250' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 2/28/73
INV. NO. 7039-W