

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Braden-Deem Inc

Complete Address 200 E 1st, Wichita, Kansas

Lease Name E. Oppy Well No. 2

Location SE NE Sec. 19 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4595'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas License No. 624

Operation Completed: Hour 11:00PM Day 21 Month 2 Year 1973

The above well was plugged as follows:

8 5/8" to 273' circulated w/ cement. 5 1/2" to 4590' cemented.

Top perforations 4505' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4440' Mud 4440' to 700'

Spotted 70 sacks cement 700' to 400' Mud 400' to 200'

Plug & 50 sacks cement 200' to 0'. Allied Pump Truck

Pulled 2250' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edna J. Egan*
Well Plugging Supervisor

INVOICED

DATE 2/28/73

INV. NO. 4040-2