

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Quality Oil Company

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name Miller Well No. 3

Location C NW NW Sec. 19 Twp. 22 Rge. 22 ~~(E)~~ (W)

County Hodgeman Total Depth 4600'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 28 Month 11 Year 1967

The Above well was plugged as follows:

8 5/8" to 278' circulated w/ cement. 4 1/2" to 4585' cemented.

Top perforations 4308' Plug bottom w/ Sand & 5 sacks cement

Top of cement 4220' Mud 4220' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 270'

Spotted 25 sacks cement 270' to 170' Mud 170' to 45'

Plug, Hlls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2501' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/30/67

INV. NO. 6800-11

Signed: *Edward A. Evers*
Well Plugging Supervisor