

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden-Deem Inc.
Complete Address 200 E 1st, Wichita, Kansas
Lease Name Jocelyn Ewy Well No. 1
Location SW SW Sec. 15 Twp. 22 Rge. 22 (S) (W)
County Hodgeman Total Depth 4443'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas License No. 624
Operation Completed: Hour 1:30PM Day 20 Month 2 Year 1973

The above well was plugged as follows:

8 5/8" to 256' circulated w/ cement. 5 1/2" to 4423' cemented.

Open hole 4423' to 4443' Plug bottom w/ sand & 5 sacks cement.

Top 4360' Mud 4360' to 700'

Spotted 70 sacks cement 700' to 400' Mud 400' to 200'

Plug & 50 sacks cement 200' to 0'. Allied Pump Truck

Pulled 3484' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Edd
Well Plugging Supervisor

INVOICED

DATE 2/28/73INV. NO. 17034-4