

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

5-7-75

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1975

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth Natl. Bank Bldg., Wichita, Kansas 67202

Lease Name Hoffman Well No. 1

Location C SW NW Sec. 11 Twp. 22 Rge. (E) (W) 22

County Hodgeman Total Depth 4455'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling

Address Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 1:45 P Day 55 Month 5 Year 1975

The above well was plugged as follows:

Total Depth 4455' 8 5/8 csg set 224' cwc 150 sx.

5 1/2 csg set 4447' cw 100 sx cem.

Filled 5 1/2 csg W/snd (4455-4300) dumped 5 sk cem W/dump bailer. (4300-4265)

Cutoff & recovered A/2800' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 21 sk gel & water W/100 lbs hulls -released

plug & 75 sk comm cem -displaced with 4 sk gel & water & capped with 20 sx comm cem.

PP 350 lbs. SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ F. Massup  
Well Plugging Supervisor

DATE 5/7/75  
INV. NO. 1275-W